#### NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS

## WARTIME REPORT

ORIGINALLY ISSUED
February 1944 as
Advance Restricted Report 4B01

A THEORETICAL INVESTIGATION OF LONGITUDINAL STABILITY

OF AIRPLANES WITH FREE CONTROLS INCLUDING EFFECT

OF FRICTION IN CONTROL SYSTEM

By Harry Greenberg and Leonard Sternfield

Langley Memorial Aeronautical Laboratory
Langley Field. Va.



#### WASHINGTON

NACA WARTIME REPORTS are reprints of papers originally issued to provide rapid distribution of advance research results to an authorized group requiring them for the war effort. They were previously held under a security status but are now unclassified. Some of these reports were not technically edited. All have been reproduced without change in order to expedite general distribution.

### ADVANCE RESTRICTED REPORT .

A THEORETICAL INVESTIGATION OF LONGITUDINAL STABILITY

OF AIRPLANES WITH FREE CONTROLS INCLUDING EFFECT.

OF FRICTION IN CONTROL SYSTEM

By Harry Greenberg and Leonard Sternfield

#### SUMMARY

The relation between the elevator hinge-moment parameters and the control forces for changes in forward speed and in maneuvers is shown for several values of static stability and elevator mass balance.

The stability of the short-period oscillations is shown as a series of boundaries giving the limits of the stable region in terms of the elevator hinge-moment param-The effects of static stability, elevator moment eters. of inertia, elevator mass unbalance, and airplane density are also considered. Dynamic instability is likely to occur if there is mass unbalance of the elevator control system combined with a small restoring tendency (high aerodynamic balance). This instability can be prevented by a rearrangement of the unbalancing weights which, however, involves an increase of the amount of weight neces-It can also be prevented by the addition of viscous friction to the elevator control system provided the airplane center of gravity is not behind a certain critical position.

For high values of the density parameter, which correspond to high altitudes of flight, the addition of moderate amounts of viscous friction may be destabilizing even when the airplane is statically stable. In this case, increasing the viscous friction makes the oscillation stable again. The condition in which viscous friction causes dynamic instability of a statically stable airplane is limited to a definite range of hinge-moment parameters. It is shown that, when viscous friction causes increasing oscillations, solid friction will produce steady oscillations having an amplitude proportional to the amount of friction.

#### INTRODUCTION

The effects of aerodynamic balance and mass unbalance of the elevator on the dynamic stability of the airplane are discussed in a previous report on control-free stability (reference 1). It was found theoretically in reference 1 and verified in flight (reference 2) that, if the elevator is too closely balanced aerodynamically and has a sufficient amount of mass unbalance (which tends to depress the elevator), increasing oscillations of short period may occur. Other flight tests (reference 3) showed, however, that mass unbalance of the elevator control system improves the static stability of an airplane, that is, increases the slope of the curve of stick force against speed in level flight and of the curve of stick force against normal acceleration in maneuvers. Subsequent work (reference  $\mu$ ) has indicated that a control surface with positive floating tendency (tendency to float against the relative wind), when used as a rudder, is effective in improving control-free static stability. A theoretical analysis (reference 5) showed that a rudder having a positive floating ratio may, under the influence of solid friction in the control system, build up steady oscillations of the airplane and rudder. These steady oscillations have been observed in flight tests (reference 6). These results suggested an investigation of the behavior of an airplane equipped with an elevator having a positive floating tendency. This type of elevator was not considered in any of the nrevious investigations.

The purpose of the present report is to make a theoretical analysis of the control-free longitudinal stability of an airplane, which takes account of this current trend toward a positive floating tendency in control-surface design and covers, in general, a much wider range of parameters than the investigation of reference 1. These parameters include, for the elevator control system, restoring tendency, floating tendency, mass unbalance (bobweight control), moment of inertia, and viscous and solid friction and, for the airplane, density and center-of-gravity position.

The method of analysis of dynamic stability is based on the classical theory of Bryan and Bairstow extended to include movements of the controls and their couplings with the airplane motions. Friction is treated in the same way as in the approximate method of reference 5, in which solid friction is replaced by an equivalent viscous friction.

Before the analysis of dynamic stability is presented, some discussion is given of the effect of the various parameters on the elevator forces for trim and for acceleration - characteristics considered important to flying qualities. The stability of the short-period oscillations, with and without friction in the control system, is then considered. The effects of weights added to the system to modify the static and dynamic stability are discussed. The trends to be expected are illustrated by a series of calculations and charts based on a typical airplane. The stability of the long-period (phugoid) oscillations is not discussed because of its relative unimportance.

#### SYMBOLS

$A_{\mathbf{W}}$	wing aspect ratio
At	tail aspect ratio
A,B,C,E,F	coefficients in stability equation
b	wing span
$c_h$	elevator hinge-moment coefficient $\left(\frac{H}{\frac{1}{2}\rho V^2 S_e c_e}\right)$
$\mathtt{c}_{\mathtt{h}_{\mathbf{f}}}$	frictional hinge-moment coefficient $\left(\frac{H_f}{\frac{1}{2}\rho V^2 S_e c_e}\right)$
$c_{h_{0}}$	applied hinge-moment coefficient .
CL	airplane lift coefficient $\left(\frac{\text{Lift}}{\text{cS}_{m}}\right)$
$\mathtt{c}_\mathtt{L_t}$	lift coefficient of tail
Cm	pitching-moment coefficient about airplane center of gravity
C	wing chord
ce	elevator chord
D	differential operator (d/ds)
<b>.</b> .	constant term in stability equation

Fs stick force

 $F_n$  stick-force gradient in maneuvers  $\left(\frac{dF_s}{dn}\right)_{dF_s}$ 

 $F_u$  stick-force gradient for level flight  $\left(\frac{dF_s}{du}\right)$ 

g acceleration of gravity

H hinge moment; positive when tends to depress trailing edge

He mass moment of elevator about its hinge; positive when tailheavy

Hs mass moment of control stick about its pivot; positive when stick tends to move forward

Hr frictional hinge moment

 $H_0 = H_0 + rH_s$ 

 $h = rh_s + h_e$ 

 $h_e = \mu E_e / \rho S_e c_e c$ 

 $h_s = 4H_s/\rho S_e c_e c$ 

Ie moment of inertia of elevator about its hinge

Is moment of inertia of control stick about its pivot

 $i_1 = i_e - ri_s$ 

 $i_2 = i_0 + r^2 i_s$ 

 $i_e = 8I_e/\rho S_e c_e c^2$ 

 $i_s = 8I_s/\rho S_e c_e c^2$ 

ky radius of gyration of airplane about Y-axis

 $k_y = 2k_y/c$ 

Ln distance between airplane center of gravity and elevator hinge

 $l_{\rm h} = 2L_{\rm h}/c$ 

ls length of control stick

m pitching moment about airplane center of gravity

m mass of airplane

N<sub>1/2</sub> number of cycles required for oscillation to damp to half amplitude

n normal acceleration per g of airplane due to curvature of flight path; accelerometer reading minus component of gravity force

P period of oscillation, seconds

q dynamic pressure

Se elevator area

St. tail area

Sw wing area

s distance in half-chords (2Vt/c)

T1/2 time required for oscillation to damp to half amplitude, seconds

t time

 $u = \Delta V/V$ 

V forward velocity

ΔV change in forward velocity from trimmed value

W weight of airplane

X longitudinal force; positive forward

xa.c. distance of center of gravity from aerodynamic center; positive when center of gravity is ahead of aerodynamic center

Z normal force; positive downward

angle of attack

at angle of attack at tail .

- deflection of elevator; positive for downward motion of trailing edge
- ā amplitude of elevator oscillation
- € angle of downwash
- r control gearing  $(\theta_s/\delta_e)$
- θ angle of pitch of airplane
- deflection of control stick; positive for forward
  motion of stick
- λ complex root of stability equation
- $\xi,\eta$  real and imaginary parts, respectively, of  $\lambda$
- $\mu$  airplane-density parameter  $(m/\rho S_w b)$
- ρ mass density of air

Whenever  $\mu$ , V,  $\alpha$ ,  $\alpha_t$ ,  $\theta$ ,  $\delta$ ,  $D\alpha$ ,  $D\theta$ ,  $D\delta$ , and  $D^2\alpha$  are used as subscripts, a derivative is indicated. For example,  $X_V = \delta X/\delta V$  and  $C_{h_{D\delta}} = \delta C_h/\delta D\delta$ . Whenever a dot is used above a symbol, it denotes differentiation with respect to time.

All angles are measured in radians.

#### METHOD OF ANALYSIS

Four degrees of freedom - forward speed, angle of attack, angle of pitch, and elevator deflection - are generally involved in the problem of control-free stability. To each degree of freedom, there corresponds an equation of equilibrium between inertial and aerodynamic forces or moments. By use of wind axes, the four equations become, for level flight,

which can be written in nondimensional form as

$$(x_{u} + 2A_{w}\mu D)u + x_{\alpha}\alpha + \frac{c_{L}}{2}\theta = 0$$

$$c_{L}u + \left(\frac{c_{L_{\alpha}}}{2} + 2A_{w}\mu D\right)\alpha - 2A_{w}\mu D\theta = 0$$

$$c_{m_{u}}u + \left(c_{m_{\alpha}} + c_{m_{D}\alpha}D + c_{m_{D}2\alpha}D^{2}\right)\alpha + \left(c_{m_{D}\theta}D - 2A_{w}\mu k_{y}^{2}D^{2}\right)\theta + \left(c_{m_{\delta}} + c_{m_{D}\delta}D\right)\delta_{\theta} = 0$$

$$c_{h_{u}}u + \left(c_{h_{\alpha}} + c_{h_{D}\alpha}D - hD + c_{h_{D}2\alpha}D^{2}\right)\alpha + \left(c_{h_{D}\theta}D + hD - h_{e}i_{h}D^{2} - i_{1}D^{2}\right)\theta + \left(c_{h_{\delta}} + c_{h_{D}\delta}D - i_{2}D^{2}\right)\delta_{\theta} = 0$$

In applying equations (1) to dynamic stability, certain approximations may be made. For instance, short-period oscillations (of the order of 1 sec) involve negligible changes in forward speed, which may therefore be neglected in studying the short-period oscillations. In fact, the period and damping of these oscillations can be obtained to a high degree of accuracy by using only the last three of the equations (1) and setting u = 0.

Equations (1) then become

$$\begin{pmatrix}
\frac{c_{L\alpha}}{2} + 2A_{w}\mu D \\
(c_{m_{\alpha}} + c_{m_{D\alpha}}D + c_{m_{D}}2_{\alpha}D^{2})\alpha & + (c_{m_{D\theta}} - 2A_{w}\mu k_{y}^{2}D)D\theta & + (c_{m_{\delta}} + c_{m_{D\delta}}D)\delta_{e} & = 0
\end{pmatrix}$$

$$\begin{pmatrix}
c_{m_{\alpha}} + c_{m_{D\alpha}}D + c_{m_{D}}2_{\alpha}D^{2}\\
c_{m_{\alpha}} + (c_{m_{D\alpha}} - h)D + c_{m_{D}}2_{\alpha}D^{2}\\
c_{m_{\alpha}} + (c_{m_{D\alpha}} - h)D + c_{m_{D}}2_{\alpha}D^{2}\\
c_{m_{\alpha}} + (c_{m_{D\alpha}} - h)D + c_{m_{D}}2_{\alpha}D^{2}\\
c_{m_{\alpha}} + (c_{m_{D\theta}} + h - (h_{e}l_{h} + i_{1})D\\
c_{m_{\alpha}} + (c_{m_{\delta}} + c_{m_{D\delta}}D - i_{2}D^{2})\delta_{e} & = 0
\end{pmatrix}$$
(2)

By setting

$$\alpha = \alpha_0 e^{\lambda t}$$
  $D\theta = (D\theta)_0 e^{\lambda t}$   $\delta_e = \delta_0 e^{\lambda t}$ 

it can be shown (reference 7) that  $\lambda$  must be a root of a quartic equation formed by writing

$$\begin{vmatrix} \frac{c_{L_{\alpha}}}{2} + 2A_{w}\mu\lambda & -2A_{w}\mu & 0 \\ c_{m_{\alpha}} + c_{m_{D\alpha}}\lambda + c_{m_{D}}2_{\alpha}\lambda^{2} & c_{m_{D\theta}} - 2A_{w}\mu ky^{2}\lambda & c_{m_{\delta}} + c_{m_{D\delta}}\lambda \\ c_{h_{\alpha}} + (c_{h_{D\alpha}} - h)\lambda + c_{h_{D}}2_{\alpha}\lambda^{2} & c_{h_{D\theta}} + h - (h_{\theta}l_{h} + i_{1})\lambda & c_{h_{\delta}} + c_{h_{D\delta}}\lambda - i_{2}\lambda^{2} \end{vmatrix} = 0$$

The resulting stability equation may be written as

$$\Delta \lambda^{4} + B \lambda^{3} + C \lambda^{2} + E \lambda + F = 0$$
 (3)

where A, B, C, E, and F are functions of the stability derivatives.

The study of the effects of different parameters on the control-free stability was made by a series of computations for an average airplane having the characteristics given hereinafter. The current trend toward a positive floating tendency in control-surface design suggests the use of  $C_{h_{\text{Cl}}}$  and  $C_{h_{\text{Cl}}}$  as the fundamental variables to be

used in expressing stability and control characteristics. The results are presented as a series of figures that show the relations between  $C_{h_{\mathfrak{A}_{\pm}}}$  and  $C_{h_{\mathfrak{F}}}$  which, with the

other derivatives fixed, satisfy the conditions for neutral dynamic stability and neutral static stability.

A curve for neutral dynamic stability is the boundary dividing the region of increasing oscillations from the region of damped oscillations and is obtained from Routh's discriminant

$$BCE - AE^2 - FB^2 = 0$$

The condition for neutral static stability is that

$$0 = \pi$$

The stability equation (3) has four roots. A pair of complex roots indicates an oscillatory mode and a real root indicates an aperiodic mode. The real part of the complex root determines the damping; the imaginary part determines the period of the oscillations. More specifically, if there is a pair of complex roots

$$\lambda = \xi \pm i\eta$$

the period in seconds is given by

$$P := \frac{c}{2V} \frac{2\pi}{\eta}.$$

and the time in seconds to damp to half amplitude is given by

$$T_{1/2} = -\frac{c}{2V} \frac{0.693}{5}$$

For an airplane at constant speed, there may be two oscillatory modes, there may be only one oscillatory mode, or the motion may be entirely aperiodic. In cases in which there are oscillatory components, one of the oscillations may be poorly damped and even become unstable.

this chara	rep		; e	rē	ъ	8,8	ed	ו ב	İS	01	ר כ	100	3 <b>V</b> E	nt	iic										
A <sub>w</sub> .		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		•		
ky .		•		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	1	•5
L <sub>h</sub> /c	= 1	h/2	<u>.</u>	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	3	.3
r.		•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	•	•	•	•	•		1
S <sub>t</sub> /S <sub>w</sub>	•	•	•	•		•	•	•	•		•	•	•	•	•	•	•		•	•	•	•		0.	18
l <sub>s</sub> , f	t.	•		•	•	•	•	•				•	•	•	•	•	•	•	•	•	•	•		•	2
S <sub>e</sub> /S <sub>t</sub>	•	•	•	•		•	•	•		•	•	•	•	•	•	•	•	•	•			•		٥.	55
At .		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•			•	4	•5
The b from appen	the	80	ai	rp	li la	ty ne	c d	er he	riv	va t ac t	il v cer	70 S	s e sti	nd .cs	l r	Э	en me	ie t	100	rs ls	o 8	bt ho	ai wn	ne 1	d n
$c_{L_{\alpha}}$ .													Cn	<sup>1</sup> D <del>0</del>	•	•	•	•		•	•	•	_	15	.3
$c_{\mathtt{Lt}_{\mathtt{at}}}$	•		•	•	•	•	•	•	. 3	<b>.</b> 8	}		Cn	lDa	: :	•	: :	•		;	:	•	•	-8	•9
εα .	•		•	•	•	•	•	C	<b>.</b> 4	<sub>1</sub> 86	5		Ch	ľDα	. •	•	•	•		•		3.	22	Ch,	αt
$c_{m_\delta}$ .	•		•	•	•	•	•	-	-1.	54	-		Cn	<sub>D</sub> 2	ά	•	•	•		•	•	•	• ?	23	.2
$\mathtt{c}_{m_{D\delta}}$	•		•	•	•	•	•	-	-0.	97	7		Ch	<sub>D</sub> 2	α	•	•	•	,	~ .	-1	07	55	C <sub>h,</sub>	αt
$\mathtt{c}_{\mathtt{h}_{D\delta}}$	(w1	th	no	f	rio	cti	.or	1).	•	-1	•														
The f	011	owi	ng	p	ar	am	e t	er	e	of	` t	he	a	ir	pl	ar	10	we	re	•	va:	ri	эđ	:	
μ airplane-density parameter																									
$c_{m_{\alpha}}$	co	ntr	ol	<b>-</b> f	ix	ьe	8	ta	ti	.c-	st	ab	11	1t	У	pe	re	me	te	r					
The f were				р	ar	am	et	er	's	of	` t	he	ө	le	va	tc	r	co	nt	r	ol.	ខ	ys:	ter	n
$c_{\mathbf{h_{a_t}}}$	Chating tendency																								
c <sub>hō</sub>	<del>-</del>																								
$\mathtt{Ch_{D\delta}}$	h <sub>Dō</sub> elevator-damping parameter																								

- ie moment-of-inertia parameter of elevator about its hinge
- is moment-of-inertia parameter of control stick about its hinge
- h mass-moment parameter of elevator control system about elevator hinge
- he mass-moment parameter of elevator alone about its hinge

As has been pointed out, the stability boundaries were plotted, in most cases, in terms of  $C_{h_{\alpha t}}$  and  $C_{h_{\delta}}$  as the variables of the coordinate system. In analyzing the effects of friction in the control system,  $C_{h_{\delta}}$  and  $C_{h_{D\delta}}$  were used as the plotted variables in some figures whereas  $C_{h_{\alpha t}}$  and  $C_{h_{\delta}}$  were used in others. The effect of the other parameters is found by varying them one at a time, through a range of values, and showing for each parameter a series of stability boundaries.

The size of the airplane, together with wing loading and altitude, are combined in the parameter  $\mu$ , which is  $\frac{m}{\rho S_W b}$ . A variation in  $\mu$  thus could be due to a variation in size, wing loading, or altitude, or any combination of these. The range of values of  $\mu$  covered in the present report together with some typical corresponding values of wing loading, altitude, and size are given in the following table:

μ	Wing loading (lb/sq ft)	Altitude (ft)	Nean wing chord (ft)				
4.17	40	Sea level	21				
12.5	40	Sea level	7				
37.5	40	33,000	7				

The range of  $C_{m_{\mathbf{Q}}}$  and the corresponding center-of-gravity positions are as follows:

C <sub>ma</sub>	xa.c. (fraction of mean wing chord)
-0.232	-0.05 0
.232	. 05

The ranges of values of the other parameters, for a small airplane (chord, 7 ft), are as follows:

i	Noment of inertia of elevator control system (slug-ft <sup>2</sup> )
0	0
2	1.6
4	3.2

·. h	Stick (1	force
TT	At sea level	At 33,000 ft
0	0	o_
10	37 ·	12==

c <sub>h<sub>D</sub>ō</sub>	dH/đồ V (1b-ft/100 mph/deg/sec)								
	At sea level	At 33,000 ft							
-10 -100	5.85 58.5	1.95 19.5							

#### STATIC STABILITY AND RELATION TO CONTROL FORCES

The connection between the static stability and the airplane and control parameters is established to assist in the interpretation of the results obtained hereinafter. Equations (1) can be applied to static stability by setting all terms containing D and D2 equal to zero and solving the resulting equations simultaneously for the variation in forward speed with an applied elevator hinge moment. For level flight, 0 is also zero and the resulting equations are

$$C_{L}u + \frac{C_{L_{\alpha}}}{2}\alpha = 0$$

$$C_{m_{u}}u + C_{m_{\alpha}}\alpha + C_{m_{\delta}}\delta_{e} = 0$$

$$C_{h_{u}}u + C_{h_{\alpha}}\alpha + C_{h_{\delta}}\delta_{e} = -C_{h_{0}}$$

Solving gives
$$-\frac{c_{h_0}}{u} = \frac{2\left(c_L c_{m_\alpha} c_{h_5} - c_L c_{h_\alpha} c_{m_5} + c_{m_6} c_{L_\alpha} \frac{c_{h_u}}{2} - c_{h_6} c_{m_u} \frac{c_{L_\alpha}}{2}\right)}{c_{L_\alpha} c_{m_5}}$$

The variation of stick force with fractional change in forward speed is

$$F_{u} = \frac{dF_{s}}{d(\Delta V/V)} = \frac{H}{l_{s}ru} = -\frac{Ch_{o}qS_{e}c_{e}}{l_{s}ru}$$
$$= \frac{\rho S_{e}c_{e}c_{g}\Lambda_{w}\mu}{l_{s}rc_{T}} \left(-\frac{Ch_{o}}{u}\right)$$

If effects of slipstream on the tail are neglected,  $c_{m_u}=0$ . As shown in appendix A,  $c_{h_u}=\frac{h c_L}{2 A_w \mu}$ . Inserting these values in the expression for  $c_{h_0}/u$  shows that  $F_u$  is independent of forward speed.

The variation of control force with normal acceleration in a steady pull-up, with no change assumed in forward speed (see reference 8), can be found from equations (2) by equating to zero all terms containing B except D0. This procedure implies that the normal acceleration is due entirely to curvature of the flight path D0. The equations become, for an applied hinge moment.

$$\frac{c_{L_{\alpha}}}{2}\alpha - 2A_{\mathbf{w}}\mu \ D\theta = 0$$

$$c_{m_{\alpha}}\alpha + c_{m_{D\theta}}D\theta \qquad \qquad \div c_{\bar{m}_{\delta}}\delta_{\mathbf{e}} = 0$$

$$c_{h_{\alpha}}c + (c_{h_{D\theta}} + h)D\theta + c_{h_{\delta}}\delta_{\mathbf{e}} = -c_{h_{0}}$$

from which

$$-\frac{c_{\mathbf{h_o}}}{D\,\theta} = \frac{-\mathrm{i} A_{\mathbf{w}\mu} c_{\mathbf{h_a}} c_{\mathbf{m_b}} - \ \mathrm{hc_{\mathbf{L_a}}} c_{\mathbf{m_b}} - \ c_{\mathbf{h_D}\theta} c_{\mathbf{L_a}} c_{\mathbf{m_b}} + \ \mathrm{i} A_{\mathbf{w}\mu} c_{\mathbf{h_b}} c_{\mathbf{m_a}} + \ c_{\mathbf{h_b}} c_{\mathbf{m_D}\theta} c_{\mathbf{L_a}}}{c_{\mathbf{L_a}} c_{\mathbf{m_b}}}$$

If the normal acceleration is ng,

$$D\theta = \frac{cng}{2V^2}$$

and

$$F_n = \frac{dF_s}{dn} = \frac{C_{h_0} \frac{1}{2} \rho V^2 S_e c_e cg}{2V^2 D\theta l_s r}$$

$$= \frac{Ch_0}{D\theta} \frac{\rho S_0 c_0 c_0}{4 l_s r}$$

These formulas for  $F_u$  and  $F_n$  are equivalent to equation (1) of reference 9 and equations (27) and (28) of reference 10.

The formulas indicate that the stick-force gradients  $F_u$  and  $F_n$  are dependent on most of the aforementioned airplane and elevator parameters. Figures 1 to 5 show the variation of these stick-force gradients with the parameters  $C_{h_{\alpha_t}}$ ,  $C_{h_{\delta}}$ ,  $C_{m_{\alpha}}$ , h, and  $\mu$ .

The gradients are independent of speed, although only within the limits of the assumptions rade in the analysis, namely, neglect of power and of compressibility effects. The gradient  $F_u$  can be used to get the stick force for only a small change in forward speed because the stick force is not directly proportional to the change in speed. The stick force in a steady pull-up  $F_n$ , however, is proportional to the normal acceleration provided the control deflection is not so great that the basic assumption of linearity is violated.

The line  $F_u=0$  is the boundary for true static stability - that is,  $F_u=0$  is the condition for zero variation in stick force with forward speed in steady flight. This condition is the same as that obtained by setting F=0, where F is the constant term of the

sixth-order stability equation obtained from equations (1). On subsequent figures it is called the divergence boundary. The line  $F_n=0$  is the boundary for apparent static (or maneuvering) stability and is the condition for zero variation in stick force in a steady pull-up. On the unstable side of  $F_u=0$ , a slow divergence occurs that is noticed by the pilot as an unstable variation of stick force with forward speed. The stick force due to normal acceleration in a pull-up is stable, however, unless the conditions are such that the airplane is operating on the unstable side of  $F_n=0$ .

Figures 1 to 5 indicate that the parameters have the same effect on  $F_{11}$  and  $F_{1n}$  except that the altitude affects only Fn. They show that the stick-force gradients on an airplane of given tail size and center-ofgravity position may be increased by making the floating Chat more positive or by mass unbalancing tendency the elevator control system to depress the elevator (make it tailheavy). The effect of the restoring tendon the stick-force gradients depends on the ency C<u>hგ</u> relative position of the center of gravity and the aerodynamic center. If the center of gravity is ahead of the aerodynamic center (airplane stable with controls fixed), increasing the magnitude of  $c_{
m h_{\delta}}$ increases the stick-force gradients. If the center of gravity is behind the nerodynamic center, this effect on Fu is reversed; the effect on Fn is not reversed, however, until the center of gravity is well behind the aerodynamic center (in this case, about 0.05c at sea level Cha = 0, the stick forces and 0.02c at 30,000 ft). If are independent of the position of the airplane center of gravity.

Increase in altitude will either increase or decrease  $F_n$ , depending on the hinge-moment parameters. The solid line in figure 5 is the locus of values of  $C_{hat}$  and  $C_{h\delta}$  for which  $F_n$  is independent of altitude. For points to the left of this line,  $F_n$  decreases with altitude; for points to the right of this line,  $F_n$  increases with altitude. This line is determined by the relation

$$c_{\mathbf{h}_{\mathbf{G}_{\mathbf{t}}}} = \frac{c_{\mathbf{m}_{\mathbf{D}\theta}}}{c_{\mathbf{m}_{\mathbf{0}}}\imath_{\mathbf{h}}} c_{\mathbf{h}_{\mathbf{0}}}$$

which, for the case of figure 5, becomes

$$c_{hat} = 1.50 c_{h\delta}$$

- - - - - - - -

Another method of increasing the stick-force gradient in level flight  $F_u$  consists in applying a constant hinge moment to the elevator by means of a spring or bungee. The effect of the spring on the gradient  $F_u$  is due to the derivative  $C_{hu}$  which depends in the same way on the constant hinge moment, whether it is caused by a weight or by a spring. A bungee, which tends to depress the elevator, will therefore increase the stickforce gradient in level flight  $F_u$ . The affect of the bungee on the stick-force gradient in accelerated flight  $F_n$  will be zero because its action depends solely on changes in forward speed. Its effect on the short-period oscillations will be zero for the same reason.

#### DYNAMIC STABILITY

#### No Friction in Control System

The stability of the short-period oscillations without friction is shown in figures 6 to 11, which also show the boundaries for true static stability (divergence boundaries). Figure 6 is an example of a more nearly complete presentation of the stability data than subsequent figures because it shows the variation of damping and period of oscillation with the hinge-moment parameters Chat and Cha for certain fixed values of the The damping, which is proportional other parameters. to  $\xi$ , increases with the magnitude of proportional to  $\frac{1}{\eta}$ , decreases as  $Ch_{\alpha t}$ Chs. The period, increases. Another way of presenting this additional stability data is shown in figure 7, which gives the number of cycles the oscillation performs before it damps to half ampli-It is clear from figure 7 that the oscillation is very well damped unless the restoring tendency is close to zero. In this particular case, only one oscillatory mode exists. Inasmuch as there are only three roots in this case (because 12 and 11 = 0), the other root is always real and is of no particular significance in dynamic stability. In cases in which an additional

oscillatory mode exists, it is always stable.

The effect of center-of-gravity position on the stability of the short-period oscillations is shown in figure 8. The shift in the dynamic-stability boundary, for the comparatively large shift in center of gravity shown, is practically negligible. Many of the subsequent figures, in which zero static stability is assumed to facilitate computation, therefore are valid for airplanes having a margin of static stability.

The effect of moment of inertia of the elevator control system on the dynamic stability is shown in figure 9, which gives typical values of the moment of inertia. The effect is slightly destabilizing especially for high values of The destabilizing effect of  $c_{h_{\alpha_+}}$ . the moment of inertia of the elevator is greater than that of the moment of inertia of the control stick. the accuracy gained by including moment of inertia is small compared with the saving in labor gained by neglecting it, moment of inertia of the elevator control system was set equal to zero in the subsequent calcula-As a result, the stability equation becomes a cubic and subsequent figures are somewhat unconservative.

The effect of density parameter  $\mu$  on the dynamic stability is shown in figure 10. Increase of  $\mu$  has a slight destabilizing effect.

As has been shown, mass unbalance of the elevator control system improves the static stability (fig. 4). The effect on dynamic stability is unfavorable, however, as shown in figure 11. The value of mass unbalance shown corresponds to a bobweight that is located at the airplane center of gravity and requires a balancing pull of 37 pounds on the control stick of a pursuit airplane at sea level. Increasing oscillations occur if the aerodynamic balance is too high (low magnitudes of Ch5), especially for negative values of Ch7.

The effect of the location of the bobweight is shown in figure 12. Each curve represents a different arrangement of bobweights and all arrangements give the same stick force. The solid line corresponds to a weight at the airplane center of gravity (for practical purposes, at the control stick). The short-dash line corresponds to a weight at the elevator. The long-dash line corresponds to a weight at the elevator, which tends

to make it noseheavy; the other at the control stick, which gives the elevator a sufficiently powerful tailheavy moment that the resultant stick force is the same as with the single weight. In the particular case represented, the noseheavy moment due to the weight at the elevator is equal to the tailheavy moment due to both weights. the single weight from the control stick to the elevator has a large destabilizing effect. Overbalancing the elevator while the stick force is kept constant has a con-This method of preventing siderable stabilizing effect. instability has the disadvantage, however, of increasing the total amount of unbalancing weight required. In the case shown, the weight is increased to three times its original size. Another disadvantage is the rearward shift in center of gravity of the whole airplane due to additional weight at the elevator. (See airplane parameters given in "Method of Analysis.") The destabilizing effect of the increased moment of inertia associated with the added weights was found to be very small, especially for negative floating tendency.

#### Effect of Viscous Friction in Control System

In the preceding section, a constant value of the elevator-damping parameter Chns was assumed. value was due only to aerodynamic damping. The effects of viscous friction in the elevator control system are obtained by considering Choh as an additional variable. This variable can be introduced, as in the preceding section, by showing a series of boundaries in the The general nature plane for various values of ChDQ. of the effect of friction is shown first, however, by presenting boundaries in the ChoChDo plane with constant and some other parameter varied. This method of presenting stability boundaries makes it easier to show the effects of other parameters such as airplane center-of-gravity position and density when friction is introduced.

The effect of viscous friction on the dynamic stability, for various conditions, is shown in figures 13 and 14 for  $\mu=12.5$  and  $\mu=37.5$ , respectively. Figures 13(a) and 14(a) refer to the mass-balanced elevator control system; figures 13(b) and 14(b) refer to the tailheavy elevator control system considered in the

preceding section. It is shown that, if the airplane center of gravity is ahead of a certain point, the instability caused by the unbalanced elevator can be removed by adding viscous friction to the control system. This critical center-of-gravity position is behind the aerodynamic center, and its distance from the aerodynamic center decreases as the density parameter µ increases. When the center of gravity is behind this critical position, viscous friction has a destabilizing effect. opposite effects of viscous friction are shown in the Chat Cho plane in figures 15 and 16. When the center of gravity is slightly ahead of this critical position, the effect of viscous friction depends on its magnitude and also on the value of  $c_{h_\delta}$ . The addition of a small amount of viscous friction is destabilizing but larger amounts are stabilizing. If the aerodynamic balance is sufficiently high (Cho = 0) and the viscous friction lies in a certain range, increasing oscillations will In figure  $H_1(\bar{b})$ , for example, if  $x_{a.c.} = -0.01c$  $C_{hg} = -0.05$ , the oscillations will be unstable when the elevator-damping parameter is in the range from -2.5 to -76. If Cha is more negative than -0.086, no amount of elevator damping can cause increasing oscillations. As the center of gravity moves forward, the destabilizing effect of elevator damping becomes less and finally disappears.

The effect of the density parameter  $\mu$  can be seen by comparing figures 13 and 14. The critical center-of-gravity position approaches the aerodynamic center as  $\mu$  increases. When  $\mu=12.5$ , elevator damping always has a stabilizing effect provided  $x_{a.c.}$  is positive. When  $\mu=37.5$ , elevator damping may be destabilizing over a small range of  $C_{hD\delta}$  and  $C_{h\delta}$  even when  $x_{a.c.}$  is positive (0.05c).

When the center of gravity is slightly shead of the afore-mentioned critical position (which is behind the aero-dynamic center), the conditions under which elevator damping may cause dynamic instability may be advantageously represented in the  $Ch_{Gt}Ch_{\bar{G}}$  plane. If a series of stability boundaries are drawn in that plane for various values of elevator damping, they will all be confined to a

Since this report was written, this point has been found to be where  $\frac{d\delta}{dn} = 0$  sometimes called the stick-fixed maneuver point.

region bounded by a line that will be called the boundary of complete damping. An illustration of two methods of constructing this boundary is given in figure 17. If a series of boundaries in the  $C_{h_{\alpha_t}}C_{h_{\delta}}$  plane are drawn for various values of the damping, the common tangent of all these curves is the boundary for complete damping. This boundary can also be drawn by plotting the minimum values of  $C_{h_{\delta}}$  obtained from plots of the type shown in figures 13 and 14 against corresponding values of  $C_{h_{\alpha_t}}$ . The region in the  $C_{h_{\alpha_t}}C_{h_{\delta}}$  plane between the boundaries for complete damping and increasing oscillations is the region where the addition of viscous friction to the elevator control system may cause dynamic instability.

That a boundary for complete damping cannot be shown for  $\mu=12.5$  if the airplane is statically neutral or stable ( $x_{a.c.}$  is zero or positive) may be seen from figure 13. It is possible, however, to show a boundary for complete damping under these conditions for  $\mu=37.5$ . Figure 18 shows these boundaries for  $x_{a.c.}=0$  and for the critical value  $x_{a.c.}=-0.017$ c, for both a massbalanced elevator and a mass-unbalanced elevator. The boundaries for increasing oscillations and divergence are also shown. For the case of the mass-balanced elevator (h = 0), the boundary for complete damping is a straight line through the origin and therefore corresponds to a fixed ratio of the floating and restoring tendencies, or floating ratio. Elevator mass unbalance decreases the region of complete damping.

· Effect of Solid Friction in Elevator Control System

The boundary for complete damping has an important bearing on the effect of solid friction on dynamic stability. In order to calculate this effect, the solid friction is replaced by an equivalent viscous friction that would dissipate energy at the same rate. This condition gives an equivalent

$$c_{h_{\overline{D}\delta}} = \frac{\mu}{\pi} \frac{c_{h_{\overline{f}}}}{n^{\overline{\delta}}} \tag{4}$$

for a sinusoidal motion of the elevator with amplitude  $\tilde{a}$  and angular frequency  $\eta_{\star}$ 

It can be shown that if viscous friction is destabilizing, as in figures 16 to 18, solid friction may lead to steady oscillations having an amplitude proportional to the amount of friction. Suppose an oscillation is started with amplitude and frequency which result in an equivalent  $\mathtt{c}_{\mathtt{h}_{\mathtt{DS}}}$ that would cause increasing oscilla-Let this condition be represented by point 2 in figure 19. The amplitude of the oscillations would then increase until the equivalent ChD6 decreased to the value that would result in neutrally damped oscillations, represented by point 3 in figure 19. If the initial amplitude is so low that the equivalent viscous friction is in the stable region, as shown by point 1, the oscillations will die out completely. If the initial amplitude is so high that the oscillations are stable, represented by point 4, the amplitude will decrease until it reaches a constant value, when the equivalent again represented by point 3. The value of at point 3 then determines the amplitude of the steady By solving formula  $(\frac{1}{4})$  for  $\overline{\delta}$ , oscillations. amplitude of the steady oscillation is obtained as

$$\overline{\delta} = \frac{l_1}{\pi} \frac{c_{h_f}}{\eta c_{h_D \delta}}$$

where  $\eta$  and  $\text{Ch}_{D\delta}$  are the values at point 3. This formula shows that the amplitude is proportional to the amount of solid friction.

The foregoing analysis shows that the region in the plane between the boundary for increasing oscil-<sup>C</sup>hαt<sup>C</sup>hδ lations and the boundary for complete damping is the region where steady oscillations may occur because of the influence of solid friction in the control system. the remarks in the preceding section concerning the boundary for complete damping with viscous friction consequently apply to the boundary for steady oscillations with solid friction, inasmuch as these two boundaries are the same, within the limits of the assumptions involved in the use of the concept of equivalent viscous friction. oscillations due to solid friction will not occur on a statically neutral or stable airplane, for instance, unless  $\mu$  is very large (corresponds to a high altitude). Even in that case, the possibility of steady oscillations exists only for a comparatively small range of floating If the airplane is statically unstable by a

high values of Cho.

sufficient amount, however, steady oscillation may exist over the entire range of floating ratio.

Some calculations of the amplitude of the steady oscillations, expressed in terms of normal acceleration per unit frictional force as felt at the control stick, were made by the method of appendix B. The results are presented in figure 20, which shows lines of constant amplitude in the  $C_{h\alpha_t}C_{h\delta}$  plane for an airplane with the center of gravity at the critical position referred to in the preceding section. Steady oscillations will therefore occur throughout the entire region where stability exists in the absence of friction. The amplitude is smallest for high values of  $C_{h\alpha_t}$  combined with

#### CONCLUDING REMARKS

The stick-free static stability of a conventional airplane may be improved by making the elevator floating tendency more positive or by mass-umbalancing the elevator control system to make the elevator tailheavy. Increasing the restoring tendency also has a favorable effect provided the airplane is stable with stick fixed. If the restoring tendency is zero, the stick-free static stability is independent of airplane center-of-gravity position.

The dynamic stability with frictionless controls depends chiefly on the restering tendency  $C_{h\delta}$  and on the mass balance of the elevator control system. If the elevator control system is mass unbalanced (elevator made tailheavy) by an offset weight at the control stick and if the restoring tendency is too low, increasing short-period oscillations may result. This condition can be remedied by the use of two additional weights - one at the elevator making it noseheavy, the other at the control stick making the elevator sufficiently tailheavy that the combined effect gives the elevator the desired amount of tailheaviness.

The addition of viscous friction to the control system will prevent dynamic instability provided the airplane center of gravity is forward of a critical position. which is behind the aerodynamic center and approaches it

as the value of the density parameter  $\mu$  increases. If the airplane center of gravity is behind this critical position, viscous friction will have a destabilizing effect, no matter what the hinge-moment parameters are. If the center of gravity is slightly ahead of the critical position, viscous friction may be destabilizing for a limited range of values of viscous friction and the hinge-moment parameters. A low restoring tendency and a high positive floating tendency will tend to cause this dynamic instability. When  $\mu$  is very large (high altitude), this condition of steady oscillations can occur even if the center of gravity is ahead of the aerodynamic center.

The presence of solid friction in the control system may cause short-period steady oscillations under the conditions for which viscous friction is destabilizing. The amplitude of the oscillations is proportional to the amount of friction present.

Langley Memorial Aeronautical Laboratory,
National Advisory Committee for Aeronautics,
Langley Field, Va.

.

. .

A Commence of the Commence of

# APPENDIX A

EVALUATION OF STABILITY DERIVATIVES

Derivative Chu - The total hinge moment acting on the elevator may be expressed as

$$H = (c_{h_0}\alpha + c_{h_0}\delta_e)\frac{1}{2}\rho v^2 s_e c_e + H_0g$$

$$H_{V} = \frac{\partial H}{\partial V} = (c_{h_{0}} a + c_{h_{0}} \delta_{e}) \rho VS_{e} c_{e}$$

At trim H = 0, therefore,

$$c_{h_{\alpha}} + c_{h_{\delta}} c_{e} = -\frac{H_{o}g}{\frac{1}{2} \rho V^{2} s_{e} c_{e}}$$

$$H_{V} = -\frac{H_{O}}{\frac{1}{2}\rho V^{2}S_{e}c_{e}}\rho VS_{e}c_{e} = -\frac{2H_{O}g}{V}$$

$$c_{h_{\mathbf{u}}} = \frac{\partial H / \frac{1}{2} \rho V^2 S_{\mathbf{e}} c_{\mathbf{e}}}{\partial V / V} = \frac{2H_{\mathbf{v}}}{\rho V S_{\mathbf{e}} c_{\mathbf{e}}} = -\frac{L_{\mathbf{H}_{\mathbf{o}}} \mathbf{g}}{\rho V^2 S_{\mathbf{e}} c_{\mathbf{e}}}$$

If 
$$H_0 = \frac{h\rho S_e c_e c}{4}$$
,

$$c_{h_u} = -\frac{heg}{v^2}$$

Using  $\frac{1}{2}\rho V^2 C_L S_W = mg$  gives

$$c_{h_{u}} = -\frac{hcg\rho c_{L}s_{w}}{2mg} = -\frac{hc_{L}}{2A_{w}\mu}$$

Derivative  $\text{C}_{m_{\text{CL}}}$  - The parameter  $\text{C}_{m_{\text{CL}}}$  may be obtained from wind-tunnel measurements or, if the position of the aerodynamic center of the complete airplane is known, may be calculated by the formula

$$c_{m_{\alpha}} = -\left(c_{L_{\alpha}} + c_{L_{t_{\alpha}}} + c_{t_{\alpha}} \frac{a_{t}}{a} \frac{s_{t}}{s_{w}}\right) x_{a.c.}$$

where

$$\frac{\alpha_t}{\alpha} = 1 - \epsilon_{\alpha}$$

 $C_{m_{\mathrm{D}\alpha}}$  and  $C_{m_{\mathrm{D}}2_{\alpha}}$ . The derivatives Derivatives and  $c_{m_D} 2_{\alpha}$ arise because of the lag between the change in angle of attack at the wing and the corresponding downwash at the tail. It is assumed that the downwash at any instant t depends on the angle of  $t - \frac{L_h}{v}$ , the difference being the attack at the instant time required for the air to move from the wing to the If  $\alpha = f(t)$ , this relation may be expressed 88

$$\epsilon = \epsilon_{\alpha} f(t - \Delta t)$$

where

$$\Delta t = L_h/V$$

$$f(t - \Delta t) = f(t) - \Delta t f'(t) + \frac{(\Delta t)^2}{2i} f''(t) - ...$$

Hence,

or, because 
$$\dot{\alpha} = \frac{2V}{C}$$
 Dq and  $\dot{\alpha} = \frac{14V^2}{C^2}$  D2a,

$$\epsilon = \epsilon_{\alpha} \left( \alpha - l_{h} D\alpha + \frac{l_{H}^{2}}{2!} D^{2}\alpha - \ldots \right)$$

and, because  $a_t = a - \epsilon$ 

$$\alpha_t = \alpha - \epsilon_{\alpha} \left( \alpha - \iota_h \, D\alpha + \frac{\iota_h^2}{2 \, \iota} D^2 \alpha - \ldots \right)$$

$$\alpha_t = \alpha(1 - \epsilon_\alpha) + \epsilon_\alpha l_h \, D\alpha - \epsilon_\alpha \frac{l_h^2}{2} \, D^2\alpha + \dots$$

The part of the pitching-moment coefficient contributed by the tail is

$$C_{m} = -C_{L_{t_{\alpha_{t}}}} \frac{l_{h}}{2} \cdot \frac{S_{t}}{S_{w}} \alpha_{t}$$

$$= -C_{L_{t_{\alpha_{t}}}} \frac{l_{h}}{2} \cdot \frac{S_{t}}{S_{w}} \left[ \alpha(1 - \epsilon_{\alpha}) + \epsilon_{\alpha} l_{h} \, D\alpha - \epsilon_{\alpha} \frac{l_{h}^{2}}{2} \, D^{2}\alpha \dots \right]$$

The lag effectively introduces derivatives  $C_{m_{D\alpha}}$ , ...  $C_{m_{D\alpha}} = -C_{L_{t\alpha}} \frac{i_{h^2}}{2} \cdot \frac{S_{t}}{S_{t}} \epsilon_{\alpha}$ 

and

$$c_{m_D 2\alpha} = c_{L_{t\alpha_t}} \frac{\iota_{h^3}}{\iota_{t}} \frac{s_t}{s_w} \epsilon_{\alpha}$$

Derivatives  $C_{h_\alpha}$ ,  $C_{h_{D\alpha}}$ , and  $C_{h_{D2_\alpha}}$ . The derivatives  $C_{h_\alpha}$ ,  $C_{h_{D\alpha}}$ , and  $C_{h_{D2_\alpha}}$  may be obtained from

$$c_h = c_{h_{\alpha_t}} \alpha_t$$

$$= c_{h_{\alpha_{t}}}(1 - \epsilon_{\alpha})\alpha + c_{h_{\alpha_{t}}}\epsilon_{\alpha}l_{h} D\alpha - c_{h_{\alpha_{t}}}\epsilon_{\alpha} \frac{l_{h}^{2}}{2} D^{2}\alpha$$

which gives

$$c_{h_{\alpha}} = c_{h_{\alpha_{t}}} (1 - \epsilon_{\alpha})$$

$$c_{h_{D\alpha}} = c_{h_{\alpha_{t}}} \epsilon_{\alpha} l_{h}$$

$$c_{h_{D} 2_{\alpha}} = -c_{h_{\alpha_{t}}} \epsilon_{\alpha} \frac{l_{h}^{2}}{2}$$

Derivative  $C_{m_{{\rm D}\theta}}$ . The pitching moment due to pitching is made up of parts due to propeller, wing, fuselage, and horizontal tail. The contribution of the tail is by far the largest and can easily be calculated.

If the airplane is rotating with angular velocity  $\theta$ , the increase in angle of attack at the tail is  $L_h \frac{\dot{\theta}}{V}$ , which results in an increased lift on the tail given (in coefficient form) by

$$c_{L_{t}} = c_{L_{t_{\alpha_{t}}}} L_{h_{\overline{V}}}.$$

The resultant pitching-moment coefficient is

$$c_{m} = -c_{L_{t}} \frac{L_{h}}{c} \frac{s_{t}}{s_{w}} = -c_{L_{t}} \frac{L_{h}}{c} \frac{\dot{\theta}}{v} \frac{L_{h}}{c} \frac{s_{t}}{s_{w}}$$

and expressing  $\theta$  as  $\frac{2V}{c}D\theta$  and  $\frac{2L_h}{c}$  as  $l_h$  gives

$$c_{m} = -c_{L_{t_{\alpha_{t}}}} \frac{l_{h}^{2}}{2} \frac{S_{t}}{S_{w}} D\theta$$

The contribution of the wing depends on the assumed axis of rotation (center of gravity) but a fair average value will be obtained by assuming that the center of gravity is at the wing quarter-chord point. This assumption gives a value

$$c_m = -\frac{\pi}{4} D\theta$$

The total pitching-moment coefficient due to pitching therefore is

$$c_{m_{D\theta}} = -\frac{\pi}{4} - c_{L_{t_{\alpha_t}}} \frac{\iota_h^2}{2} \frac{s_t}{s_w}$$

Derivative  $C_{m\delta}$ . The derivative  $C_{m\delta}$  may be measured directly in a wind tunnel or may be computed from wind-tunnel data on the value of  $C_{Lt\delta}$  for the horizontal tail by means of the formula

$$c_{m\delta} = -c_{L_{t\delta}} \frac{i_h}{2} \frac{s_t}{s_w}$$

Derivative  $c_{mD\delta}$  .- The derivative  $c_{mD\delta}$  may be computed from

$$c_{m_{D\delta}} = - \left[ \frac{\delta c_L}{\delta D \delta} \right]_A + c_{L_{t_{\alpha}}} \left( \frac{\delta c_L}{\delta D \delta} \right)_{\underline{B}} \frac{l_h}{2} \frac{s_t}{s_w} \frac{c_t}{c}$$

where  $\left(\frac{\partial C_L}{\partial D\delta}\right)_A$  and  $\left(\frac{\partial C_L}{\partial D\delta}\right)_B$  may be obtained from figure 1 of reference 11, which is based on thin-wing potential-flow theory.

Derivative  $C_{hD\theta}$  - The derivative  $C_{hD\theta}$  is given by

$$c_{h_{D\theta}} = c_{h_{\alpha_t}} \iota_h$$

In the absence of viscous friction in the elevator control system, the value of  $c_{\rm hD\delta}$  may be computed from

$$c_{h_{D\delta}} = -\left[\left(\frac{\partial c_{h}}{\partial D\delta}\right)_{A} + c_{L_{t_{\alpha_{t}}}}\left(\frac{\partial c_{h}}{\partial D\delta}\right)_{B}\right] \frac{c_{t}}{c}$$
(A1)

where  $\left(\frac{\partial C_h}{\partial D\delta}\right)_A$  and  $\left(\frac{\partial C_h}{\partial D\delta}\right)_B$  may be obtained from figure 1 of reference 11.

If a dashpot, which has a damping constant of K pounds per foot per second and moves a distance of Q feet per radian of elevator deflection, is inserted in the control system,

$$c_{h_{D\delta}} = \frac{\mu_Q^2 \kappa}{\rho V S_e c_e c}$$
 (A2)

The total value of  $C_{hD\delta}$  is the sum of equations (A1) and (A2).

Derivatives  $C_{h_{\alpha_t}}$  and  $C_{h_{\delta}}$ . The derivatives  $C_{h_{\alpha_t}}$  and  $C_{h_{\delta}}$  can be calculated by thin-wing-section theory but the results are of doubtful accuracy because of three-dimensional and boundary-layer effects. It is therefore best to obtain these derivatives from wind-tunnel tests.

#### APPENDIX E

#### CALCULATION OF NORMAL ACCELERATION DUE TO OSCILLATING ELEVATOR

The normal acceleration of the airplane, which is equal to  $D(\alpha - \theta)$  in non-dimensional units, can be calculated from

$$\frac{D(\alpha - \theta)}{\delta} = \frac{-c_{mg}c_{L_{tc}} - c_{L_{tc}}c_{mD\delta}r_{i}1}{2\left[\frac{c_{mD\theta}c_{L_{tc}}}{2} - 2A_{\mu}\mu c_{m\alpha} - \eta^{2}(\mu A_{w}^{2}\mu^{2}k_{y}^{2} - c_{mD}^{2}\alpha^{2}A_{v}\mu) + 1r_{i}\left(-2A_{w}\mu c_{mD\theta} + 2A_{w}\mu k_{y}^{2} - 2A_{w}\mu c_{mD\theta}\right)\right]}$$
(B1)

where  $\tilde{\eta}$  is the engular frequency of the elevator.

The fraction in equation (B1) can be reduced to an ordinary complex number and the modulus of this number is the maximum amplitude of the steady oscillation. The value can be converted to physical units by the formula

Normal acceleration per 
$$g = \frac{4l_{s}r}{\rho s_{o}c_{e}c_{g}} \frac{D(\alpha - \theta)}{\delta} \frac{l_{t}}{m_{t}c_{h}}$$

where  $c_{h_{D\delta}}$  is the value of elevator damping required for the condition of neutral dynamic stability.

١

#### REFERENCES

- 1. Jones, Robert T., and Cohen, Doris: An Analysis of the Stability of an Airplane with Free Controls. Rep. No. 709, NACA, 1941.
- 2. Phillips, William H.: A Flight Investigation of Short-Period Longitudinal Oscillations of an Airplane with Free Elevator. NACA ARR, May 1942.
- 3. Phillips, Tilliam H.: Effect of Spring and Gravity Moments in the Control System on the Longitudinal Stability of the Brewster XSBA-1 Airplane. NACA ARR. April 1942.
- 4. Jones, Robert T., and Klecknor, Harold F.: Theory and Preliminary Flight Tests of an All-Moveble Vertical Tail Surface. FACA ARR, Jan. 1943.
- 5. Greenberg, Harry, and Sternfield, Leonard: A Theoretical Investigation of the Lateral Oscillations of an Airplane with Free Rudder with Special Reference to the Effect of Friction. NACA ARR, March 1943.
- 6. Klecknor, Harold F.: Flight Tests of an All-Movable Vertical Tail on the Fairchild XR2K-1 Airplanc. NACA ACR No. 3F26, June 1943.
- 7. Jones, B. Melvill: Dynamics of the Airplane. The Equations of Metion with Solutions for Small Disturbances from Steady Symmetric Flight. Vol. V of Acrodynamic Theory, div. N, ch. V, secs. 22-31, W. F. Durand, ed., Julius Springer (Berlin), 1935, pp. 135-141.
- 8. Gilruth, R. R.: Requirements for Satisfactory Flying Qualities of Airplanes. NACA ACR, April 1941. (Glassification changed to "Restricted" Oct. 1943.)
- 9. Gates, S. B.: Proposal for an Elevator Manoeuvrability Critorion. Rep. No. Acro. 1740 (Revised), R.A.E., June 1942.
- 10. White, Roland J.: A New Method of Longitudinal Control for Aircraft by Use of an Adjustable Angle of Attack. Balanco. Jour. Acro. Sci., vol. 10, no. 5, May 1943, pp. 152-160.
- 11. Cohon, Doris: A Thorestical Investigation of the Rolling Oscillations of an Airplane with Ailcrons Free. NACA ARR No. 4406, Jan. 1944.




Figure 1.- Trim force  $\mathbb{F}_u$  and pull-up force  $\mathbb{F}_n$  as a function of hingemoment parameters. xa.c. = 0.05c;  $\mathbb{V}/S_{\mathbb{W}}$  = 40 pounds per square foot; c = 7 feet; sea level.  $\mathbb{F}_u$  = stick force in pounds for  $\Delta \mathbb{V}/\mathbb{V}$  = 1.0;  $\mathbb{F}_n$  = stick force in pounds per g normal acceleration.




Figure 2.- Trim force  $F_u$  and pull-up force  $F_n$  as a function of hingemoment parameters.  $x_{a.c.} = 0$ ;  $\mathbb{W}/S_{\mathbb{W}} = 40$  pounds per square foot; c = 7 feet; sea level.  $F_u = \text{stic.}$  force in pounds for  $L\mathbb{V}/\mathbb{V} = 1.0$ ;  $F_n = \text{stick}$  force in pounds per g normal acceleration.




Figure 3.- Trim force  $F_u$  and pull-up force  $F_n$  as a function of hingemoment parameters.  $x_{a.c.} = -0.05c$ ;  $\mathbb{W}/S_w = 40$  pounds per square foot; c = 7 feet; sea level.  $F_u = \mathrm{stick}$  force in pounds for  $\Delta \mathbb{W}/\mathbb{W} = 1.0$ ;  $F_n = \mathrm{stick}$  force in pounds per g normal acceleration.




Figure 4.- Trim force  $F_u$  and pull-up force  $F_n$  as a function of hingemoment parameters. Mass-unbalanced elevator (h = 10);  $\mathbf{x}_{a.c.} = 0.05c$ ;  $\mathbf{W/S_W} = 40$  pounds per square foot; c = 7 feet; sea level.  $F_u = \text{stick}$  force in pounds for  $\Delta \mathbf{V/V} = 1.0$ ;  $F_n = \text{stick}$  force in pounds per g normal acceleration.

Figure 5.- Effect of altitude on values of stick-force gradient.  $x_{a.c.} = 0.05c; \text{ W/S}_w = 40 \text{ pounds per square foot;}$  c = 7 feet.






Fig. 6




Figure 7.- Number of cycles to damp to half amplitude N against hinge-moment parameters.  $x_{a.c.}$  = 0;  $\mu$  = 12.5; h = i = 0.

Figure 8.- Effect of center-of-gravity location on stability boundaries.  $\mu$  = 12.5.

Restoring tendency, Ch8




Figure 9.- Effect of elevator-control-system moment of inertia on the boundary for increasing oscillations.  $\mu$  = 12.5.




Figure 10.- Variation of stability boundaries with density parameter.




Figure 11.- Effect of mass unbalance of the elevator control system on the stability boundaries.  $\mu$  = 12.5.





Figure 12.- Effect of location of mass unbalance of the elevator control system on the stability boundaries.  $\mu$  = 12.5;  $i_e$  = 0;  $i_s$  = 0.







Figure 13.- Effect of elevator damping on the boundary for increasing oscillations for various center-of-gravity locations and elevator-mass-balance conditions.  $Ch_{\alpha_t}=0.1$ ;  $\mu=12.5$ .





NACA

Figure 14.- Effect of elevator damping on the boundary for increasing oscillations for various center-of-gravity locations and elevator-mass-balance conditions.  $Ch_{ct} = 0.1$ ;  $\mu = 37.5$ 




Figure 15.- Illustration of stabilizing effect of elevator damping (viscous friction).  $x_{a.c.}$  = 0;  $\mu$  = 12.5; h = 10.






Figure 16.- Illustration of destabilizing effect of elevator damping (viscous friction).  $x_{a.c.} = -0.05c$ ;  $\mu = 12.5$ ; h = 10.




Figure 17 .- Method of constructing boundary for complete damping.






Figure 18.- Boundaries for complete damping, increasing oscillations, and divergence,  $\mu$  = 37.5.




Figure 19 .- Effect of solid friction in building up steady oscillations.




Figure 20.- Variation of maximum normal acceleration in the steady oscillation with elevator hinge-moment parameters.  $x_{a.c.} = -0.05c$ ;  $\mu = 37.5$ ; h = 10;  $i_e = 2$ ;  $i_s = 0$ .

NASA Technical Library
3 1176 01417 1038